

EverGlo Propane Gas Service**JOB ESTIMATE**

2215 Gillionville Road
Albany, GA 31707

www.everglopropane.com
229-439-4540

TO:

Mary Addison ACCOUNT # 01-02010
200 Hicks Rd. Dawson GA 39842

**JOB DESCRIPTION**

This is an estimate on the installation (Gas, Electrical & Plumbing) of a Rinnai RE159. Including all labor and expected materials.

ITEMIZED ESTIMATE: TIME AND MATERIALS		AMOUNT
Quantity	Material	Cost
20'	3/4" poly (Blue)	\$30.56
20'	3/4" poly (Red)	\$30.56
2	3/4" Sharkbite Coupling	\$61.43
2	3/4" Poly Crimp 90	\$13.16
3	3/4" Male Adapter (Crimp to Poly)	\$24.66
10	Crimp Rings	\$20.00
1	Rinnai Model # RE159	\$1,587.60
1	Rinnai Plumbing Cover Box	\$207.20
1	Rinnai Plumbing Kit	\$105.00
1	2nd Stage Regulator #3571011	\$77.02
1	Dielectric Union #1k122a	\$17.43
1	1/2" Brass Flare Tee #5k072	\$9.90
1	3/4" Shutoff Valve #2k271	\$21.65
1	3/4" x 18" Galvanized Pipe Nipple #1k122g	\$17.03
1	3/4" x 1/2" Flare Adapter #5k412	\$6.66
4	1/2" Flare Nuts #5k412	\$14.40
1	15 Amp Square D Home Line Breaker	\$25.00
1	Outside Box w Cover	\$25.00
1	Electric Cord	\$25.00
	Misc. Supplies & Fittings	\$50.00
	Tax (8%)	\$189.54
	Sub-Total \$2558.80	
6 HR	Labor - 2 men	\$900.00
	Rinnai Rebate	-\$200.00
	Totals are only an estimate, prices & quantities may vary depending on labor & materials.	
This estimate ONLY GOOD 30 days from day written		
Payment due upon completion of job. Keep in mind any card will be charged a 3.75% convenience fee.		
NO FEE FOR CASH OR CHECK. Also pay on our website at the top of this page, with your account #!		

TOTAL ESTIMATED JOB COST \$3,258.80

This is an estimate only, not a contract. This estimate is for completing the job described above, based on our evaluation. It does not include unforeseen price increases or additional labor and materials which may be required should problems arise.

Barry Vann & Chance Greene
PREPARED BY

4/7/2025
DATE